

Item	Site Built Home Measures and Description	Labor	Material	Total
	Health and Safety			
	Smoke Detectors (UL Listed, Battery Powered)			
	Dryer Vent - Hood Only			
	Dryer Vent - Hose Only (Rigid and/or UL Approved Flex)			
	Dryer Vent - Replace Existing - Simple			
	Dryer Vent - New or Replace Existing - Complex			
	Combustion Air Grills - High & Low, Front Only			
	Combustion Air Grills - High & Low, Front & Rear			
	Exhaust Existing Bath/Kitchen Fan Through Roof (Insulated Flex for Duct)			
	Replace Existing Bath/Kitchen Fan - Complete			
	Carbon Monoxide Monitor			
	Major Bypass - Infiltration - Doors & Windows			
	Steel Entry Door Replacement - Pre-Hung Only, Unless Specified Includes Casing, Peep Viewer & Deadbolt Lock Set			
	Replace Door Wall			
	Adjust/Repair Existing Door - Simple			
	Adjust/Repair Existing Door - Complex			
	Wood Door Weather-Strip			
	Aluminum Door Weather-Strip			
	Bump Threshold			
	Door Sweep			
	Lockset without Deadbolt			
	Lockset with Deadbolt			
	Conversion Kit			
	Remove & Replace Existing Storm Door (Per Hr.)			
	Storm Door Pump			
	Storm Door Chain			
	Storm Door Handle			
	Storm Door Kit			
	Window Sealing (Ea. Window)			
	Sash Lock			
	Window Kit			
	Replacement Window - Vinyl Thermal Low-E (Per Sq. Ft.)			
	Outside-Operable Storm (Per Sq. Ft.)			
	Major Bypass - Infiltration - Misc. Air Sealing			
	Bypass Sealing - Kraft-Faced Insulation or Air Seal Bags			
	Bottom of Slopes (Per Ln. Ft.)			
	Under Knee Wall (Per Ln. Ft.)			
	Balloon Framing (Per Ln. Ft.)			
	Seal & Insulate Milk Chute			
	Misc. Air Sealing - Time & Materials			
	Drywall (Per Hr.)			
	Paneling (Per Hr.)			
	Plywood (Per Hr.)			
	Caulk (Per Hr.)			
	Spray Foam (Per Hr.)			
	2-Part Spray Foam for Air Sealing - R-7, 1" Thickness (Per Sq. Ft.)			
	Fireplace Plugs			
	Fan Treatment with Eye Hooks & Rope			
	Vinyl Cover for Whole House Fan - Inside			

Item	Site Built Home Measures and Description	Labor	Material	Total
Major Bypass - Infiltration - Attic Access				
	Ceiling Access - New			
	1 x 4, 3/4 CDX, Foam W/S, Insul. Pillow			
	Ceiling Access - Existing Opening			
	1 x 4, 3/4 CDX, Foam W/S, Insul. Pillow			
	Weather-Strip & Insulate Only			
	Plywood, Weather-Strip & Insulate			
	Knee Wall Door - New			
	1 x 4, 3/4 CDX, 2 Hinges, 1 Barrel Bolt, Insul. Pillow, Wood W/S, Threshold/Sweep			
	Knee Wall Door - Existing Opening			
	1 x 4, 3/4 CDX, 2 Hinges, 1 Barrel Bolt, Insul. Pillow, Wood W/S, Threshold/Sweep			
	Air Seal & Insulate Existing Attic Access			
	Pull Down Stair Treatment - 2" Foam Board, 3/4 Plywood			
Major Bypass - Infiltration - Crawl Space Access				
	Crawl Space Access - New			
	3/4 Wolmanized Plywood, 2 x 8 Wolmanized, 2 Zinc Barrel Bolts, W/S, Insul. Pillow			
	Crawl Space Access - Existing Opening			
	3/4 Wolmanized Plywood, 2 x 8 Wolmanized, 2 Zinc Barrel Bolts, W/S, Insul. Pillow			
	Air Seal & Insulate Existing Access			
Duct Seal - Repair and Replacement				
	New Pan End for Return Air Ducts (Per Hr.)			
	Mastic Holes & Gaps in Ductwork (Per Hr.)			
	Seal Return Air Register at Furnace (Per Hr.)			
Duct Insulation				
	Duct Insulation (R-8 Minimum) (Per Sq. Ft.)			
	Pipe Insulation (R-3.5 Minimum) (Per Ln. Ft.)			
Exterior Wall Insulation				
	Blown Cellulose R-13: Siding Single Story (Per Net Sq. Ft.)			
	Blown Cellulose R-13: Siding Second Story (Per Net Sq. Ft.)			
	Blown Cellulose R-13: Brick Single Story (Per Net Sq. Ft.)			
	Blown Cellulose R-13: Brick Second Story (Per Net Sq. Ft.)			
	Fiberglass Batts - Open Wall R-13 (Per Net Sq. Ft.)			
	Injection Foam (Per Net Sq. Ft.)			
	Sided, Single Story			
	Sided, Two Story			
	Brick, Single Story			
	Brick, Two Story			
	10" Block: Fill Core			
	12" Block: Fill Core			
Attic Insulation				
	Open Attic: Blown Cellulose R-11 (Per Sq. Ft.)			
	Open Attic: Blown Cellulose R-19 (Per Sq. Ft.)			
	Open Attic: Blown Cellulose R-30 (Per Sq. Ft.)			
	Open Attic: Blown Cellulose R-38 (Per Sq. Ft.)			
	Open Attic: Blown Cellulose R-49 (Per Sq. Ft.)			
	Open Attic: Blown Fiberglass R-11 (Per Sq. Ft.)			
	Open Attic: Blown Fiberglass R-19 (Per Sq. Ft.)			
	Open Attic: Blown Fiberglass R-30 (Per Sq. Ft.)			
	Open Attic: Blown Fiberglass R-38 (Per Sq. Ft.)			
	Open Attic: Blown Fiberglass R-49 (Per Sq. Ft.)			
	Open Attic: Fiberglass Batts R-13 (Per Sq. Ft.)			
	Open Attic: Fiberglass Batts R-19 (Per Sq. Ft.)			
Page 2				
	Open Attic: Fiberglass Batts R-30 (Per Sq. Ft.)			

Item	Site Built Home Measures and Description	Labor	Material	Total
	Open Attic: Fiberglass Batts R-38 (Per Sq. Ft.)			
	Open Attic: Fiberglass Batts R-49 (Per Sq. Ft.)			
	Knee Walls: Fiberglass Batts R-13 (Per Sq. Ft.)			
	Knee Walls: Fiberglass Batts R-19 (Per Sq. Ft.)			
	Slopes: Tube Slopes to Dense Pack Blown Cellulose R-13 (Per Sq. Ft.)			
	Slopes: Tube Slopes to Dense Pack Blown Cellulose R-19 (Per Sq. Ft.)			
	Additional Attic Insulation / Ventilation			
	Attic Preparation			
	Insul Shield Exhaust Fans, Chimneys, Knob & Tube, Recessed Cans, Open Wiring (Per Hr.)			
	Insulation Barrier - 1/2" CDX at All Scuttle Type Accesses (Ea.)			
	Slash Existing Vapor Barrier (Per Sq. Ft.)			
	Remove Existing Insulation (Per Sq. Ft.)			
	Drill/Lift Boards to Insulate (Per Hr.)			
	50 Sq. In. Slant Back Roof Vent			
	50 Sq. In. Slant Back Roof Vent, 2nd Story			
	Soffit Vent, Includes Chute, 1st Story			
	Soffit Vent, Includes Chute, 2nd story			
	Soffit Vent Chute (Ea.)			
	Recessed Light Covers (Ea.)			
	Foundation Insulation			
	Fiberglass Batts R-13 to Floor Joist Cavities - Includes Fiberglass Supports (Per Sq. Ft.)			
	Fiberglass Batts R-19 to Floor Joist Cavities - Includes Fiberglass Supports (Per Sq. Ft.)			
	Fiberglass Batts R-30 to Floor Joist Cavities - Includes Fiberglass Supports (Per Sq. Ft.)			
	Fiberglass Batts R-13 to Perimeter Foundation Walls & 2' Out (Per Sq. Ft.)			
	Fiberglass Batts R-19 to Perimeter Foundation Walls & 2' Out (Per Sq. Ft.)			
	Unfaced Fiberglass R-19 to Basement/Crawl Space Box Sills (Per Ln. Ft.)			
	6 Mil Visqueen on Ground - Overlap & Tape Seams 12" & 6" Up Foundation Wall (Per Sq. Ft.)			
	4" Rigid Foam Insulation R-10 Minimum (Per Sq. Ft.)			
	Additional Foundation Insulation / Ventilation			
	Foundation Vent - Replace Existing			
	Foundation Vent - New Opening			
	Compact Fluorescent Light Bulbs			
	5 Watt CFL (Ea.)			
	7 Watt CFL (Ea.)			
	9 Watt CFL (Ea.)			
	13 Watt CFL (Ea.)			
	18 Watt CFL (Ea.)			
	25 Watt CFL (Ea.)			
	26 Watt CFL (Ea.)			
	38 Watt CFL (Ea.)			
	11 Watt Flood CFL (Ea.)			
	15 Watt Flood CFL (Ea.)			
	18 Watt Flood CFL (Ea.)			
	Additional Weatherization Measures			
	Blower Door Test (Per Unit)			
	Hourly Weatherization Rate - General Labor			